


PARTIAL SPINE & FINGER STRUCTURAL FOUNDATION PLAN - AREA A2

1 / S101.1A2

Scale: 1/16" = 1'-0"

FOUNDATION PLAN NOTES:

1. SEE SHEET S020 FOR SLAB-ON-GROUND DETAILS. T/SLAB-ON-GROUND ELEVATION ABOVE MEAN SEA LEVEL = 845'-0" TO BE DATUM ELEVATION = +0'-0".
2. SEE S101.1OF FOR FOUNDATION DETAILS AT OFFICE BUMP-OUT.
3. MAXIMUM CONTRACTION JOINT SPACING = 15'-0", SEE SHEET S501 FOR CONTROL AND CONSTRUCTION JOINT DETAILS.
4. FOR DOOR OPENING SIZES AND LOCATIONS IN EXTERIOR WALLS SEE ARCHITECTURAL DRAWINGS.
5. FOR SLAB AND FOUNDATION PENETRATIONS, SEE MECHANICAL, ELECTRICAL, AND PLUMBING DRAWINGS.
6. COORDINATE LOCATIONS, SIZES AND TYPES OF SLAB DEPRESSIONS, EQUIPMENT PADS, EMBEDMENTS AND PENETRATIONS WITH THE ARCHITECTURAL, MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS.
7. PERIMETER FOUNDATION WALL LOCATION TO COORDINATE WITH WALL PANEL THICKNESS.
8. "FS" DENOTES FOOTING STEP, SEE 23/S501. COORDINATE LENGTH & LOCATION OF FOOTING STEP WITH CONCRETE WALL PANEL LAYOUT.
9. "CX" DENOTES COLUMN MARK. SEE SCHEDULE ON THIS SHEET.
10. "FX" DENOTES FOOTING MARK. SEE SCHEDULE ON THIS SHEET.
11. CANOPY FOUNDATIONS DESIGNED BY CANOPY MANUFACTURER (SIZE SHOWN AS PLACEHOLDER). COORDINATE FINAL LOCATION AND SIZE OF CANOPY FOUNDATIONS TO AVOID UNDERMINING BUILDING FOUNDATIONS.
12. PROVIDE KNOCKOUT PANELS IN WALL FOR FUTURE DOCK DOOR OPENINGS AT THIS END OF FINGERS, SEE ARCH DRAWINGS AND S800 FOR REINFORCING AROUND FUTURE OPENINGS.

TABLE 1
MINIMUM LAP SPLICE AND ANCHORAGE DIMENSION TABLE

USE THIS TABLE FOR ASTM A615 GRADE 60-UNCOATED REINFORCING WHEN CONCRETE CLEAR COVER IS 1" OR MORE AND BAR CLEAR SPACING IS LESS THAN THREE (3) BAR DIAMETERS. IN ALL OTHER CASES USE TABLE #1B. IF CONCRETE CLEAR COVER IS LESS THAN 1", LAP AND ANCHORAGE LENGTHS SHALL BE CALCULATED PER ACI 318.

	(4000 or 4500 PSI CONCRETE) TOP BARS		OTHER BARS			(3000 PSI CONCRETE) TOP BARS		OTHER BARS	
BAR SIZE	LAP	ANCH	LAP	ANCH	BAR SIZE	LAP	ANCH	LAP	ANCH
#3	20"	16"	16"	12"	#3	23"	18"	18"	14"
#4	33"	25"	25"	19"	#4	38"	29"	29"	22"
#5	47"	36"	36"	28"	#5	54"	42"	42"	32"
#6	62"	48"	48"	37"	#6	72"	55"	55"	43"
#7	99"	76"	76"	59"	#7	114"	88"	88"	68"
#8	121"	93"	93"	72"	#8	139"	107"	107"	83"
#9	136"	105"	105"	81"	#9	157"	121"	121"	93"
#10	153"	118"	118"	91"	#10	177"	136"	136"	105"
#11	(MC)	131"	131"	101"	#11	(MC)	151"	151"	116"

2 / S101.1A2 — 03 30 00 TABLE 1 — NTS

TABLE 1 NOTES:

A. (MC) DENOTES MECHANICAL COUPLER DEVELOPING 125% OF THE BAR YIELD STRENGTH. NO OTHER SPLICE WILL BE ACCEPTED.
B. WHEN LAPPING TWO DIFFERENT SIZE BARS, USE THE LAP DIMENSION OF THE SMALLER BAR OR THE ANCHORAGE DIMENSION OF THE LARGER BAR. USE WHICHEVER DIMENSION IS LARGER.
C. TOP BARS SHALL BE DEFINED AS BEAM AND SLAB HORIZONTAL REINFORCEMENT SO PLACED THAT MORE THAN 12" OF FRESH CONCRETE IS CAST IN THE MEMBER BELOW THE TOP REINFORCEMENT. HORIZONTAL REINFORCING IN WALLS SHALL BE CONSIDERED TOP BARS.

FOOTING SCHEDULE


FOOTING MARK	SIZE (LxWxH)	REINFORCING (BOTTOM, UNO)	REFERENCE
F4	4'-0"x4'-0"x1'-6"	w/ (10) - #5 Bars Each Way	
F5	5'-0"x5'-0"x1'-9"	w/ (11) - #5 Bars Each Way	
F6	6'-0"x6'-0"x1'-9"	w/ (8) - #6 Bars Each Way	
F7	7'-0"x7'-0"x2'-0"	w/ (9) - #6 Bars Each Way	
F8	8'-0"x8'-0"x2'-0"	w/ (10) - #6 Bars Each Way	
F8A	8'-0"x8'-0"x1'-9"	w/ (9) - #6 Bars Each Way Top & Bottom	
F9	9'-0"x9'-0"x2'-6"	w/ (14) - #6 Bars Each Way	
F10	10'-0"x10'-0"x2'-6"	w/ (11) - #7 Bars Each Way	4
F10A	10'-0"x10'-0"x3'-0"	w/(18) - #6 Bars Each Way Top & Bottom	
F11	11'-0"x11'-0"x2'-6"	w/ (14) - #7 Bars Each Way	
F12	12'-0"x12'-0"x3'-0"	w/ (13) - #8 Bars Each Way Top & Bottom	
F13	13'-0"x13'-0"x4'-0"	w/ (18) - #8 Bars Each Way Top & Bottom	
F14	14'-0"x14'-0"x3'-0"	w/ (14) - #8 Bars Each Way Top & Bottom	
F14A	14'-0"x14'-0"x4'-0"	w/ (20) - #8 Bars Each Way Top & Bottom	
F15	15'-0"x15'-0"x4'-0"	w/ (21) - #8 Bars Each Way Top & Bottom	
F16	16'-0"x16'-0"x4'-0"	w/ (24) - #8 Bars Each Way Top & Bottom	
F18	18'-0"x18'-0"x4'-0"	w/ (25) - #8 Bars Each Way Top & Bottom	
F19	19'-0"x19'-0"x4'-0"	w/ (25) - #8 Bars Each Way Top & Bottom	
F20	20'-0"x20'-0"x4'-0"	w/ (27) - #8 Bars Each Way Top & Bottom	

COLUMN SCHEDULE

ALL COLUMNS WITH A FLANGE THICKNESS EXCEEDING 2 INCHES SHALL BE SUPPLIED WITH SUPPLEMENTARY CHARPY V-NOTCH REQUIREMENT S30.

COLUMN MARK	COLUMN SIZE	BASEPLATE SIZE (t x W x L)	Description
C1	HSS12x12x5/8	2" x 18" x 18"	
C1A	HSS12x12x1/2	1 1/2" x 18" x 18"	
C1B	HSS10x10x1/2	1"x 18" x 18"	
C2	W14x257	3 1/2" x 30" x 42"	
C3	W14x233	4" x 23" x 45"	
C4	W14x257	4" x 23" x 45"	
C5	W14x311	4" x 30" x 45"	
C6	W14x211	3 1/2" x 30" x 42"	
C7	W14x211	3"x 23"x 48"	
C8	W14x211	4 3" x 23" x 48"	
C9	WTGx68	1" x 11" x 16"	
C10	W12x152	2" x 16" x 16"	
C11	HSS6x6x5/16	1" x 12" x 12"	
C12	HSS8x8x5/16	1" x 14" x 14"	
C13	W14x257	4" x 23" x 45"	

KEYPLAN



AECOM

PROJECT

HUMMINGBIRD

CENTRAL HUB GEN1.0 V1.1

2134 BLUE CREEK ROAD
HOGANSVILLE, GA 30230

CLIENT

SEEFRIED DEV. MANAGEMENT INC.
3333 RIVERWOOD PKWY, SUITE 200
ATLANTA, GA 30339

ARCHITECT

ARCHITECT OF RECORD
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

ENGINEERS/CONSULTANTS

STRUCTURAL
AECOM
277 Nationwide Blvd
Columbus, OH 43215
281.646.2400 tel
www.aecom.com

MEP
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

IT / SECURITY
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

FIRE PROTECTION / ALARM
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

REGISTRATION

GEORGIA REGISTERED No. SE 001795 PROFESSIONAL ENGINEER ANDREW L. MAPHIS 3-07-25

03/07/2025

REV	DATE	ISSUED BY	ISSUED TO	DESCRIPTION
1	11/15/2024	AECOM	JHU	ISSUE FOR BID & PERMIT
4	03/07/2025	AECOM	ATHENA	ADDENDUM #3

PROJECT NUMBER

60735057

SHEET TITLE

PARTIAL SPINE & FINGER STRUCTURAL FOUNDATION PLAN - AREA A2

SHEET NUMBER

S101.1A2


This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

© 2024 AECOM Corporation

Printed on ___% Post-Consumer Recycled Content Paper

3/6/2025 1:01:40 PM Autodesk Docs://BP-AMER (USA) 60735057 - ATS-GAZ5_Central Hub/60735057_ACM_R23_GAZ5_S.rvt
Project Management Initials: JA Designer: GK Checked: NH Approved: ALK ARCH E1 30"x42"

ARCH E1 30"x42"
Approved: ALK
Checked: WH
Designer: GK
Project Management Initials: JA



PARTIAL SPINE 2ND FLOOR FRAMING PLAN - AREA B1


1 — S101.2B1

Scale: 1/16" = 1'-0"

2ND FLOOR FRAMING PLAN NOTES:

1. TOP OF STEEL ELEVATION FOR 2ND FLOOR CONSTRUCTION IS (+25'-6") ABOVE DATUM FIRST FLOOR SLAB ELEVATION, UNLESS NOTED OTHERWISE BY +/- FROM 2ND FLOOR ELEVATION.
2. SEE DECK SCHEDULE ON S600 FOR FLOOR CONSTRUCTION DETAILS.
3. THE STEEL FABRICATOR SHALL DESIGN END SHEAR CONNECTIONS TO RESIST LRFD END REACTIONS DENOTED AS V=XXK ON BEAM LABELS. SEE TABLES ON SHEET S512 FOR REACTIONS NOT SHOWN.
4. FOR SIZES AND LOCATIONS OF FLOOR PENETRATIONS, SEE ARCHITECTURAL, MECHANICAL, AND PLUMBING DRAWINGS. MAJOR PENETRATIONS ARE DETAILED ON PLAN. FOR MINOR PENETRATIONS COOR LOCATIONS AND SIZE w/ ARCH/MEP/MHE AND SEE 2/S511 FOR APPLICABLE FRAMING DETAILS.
5. (XX) DENOTES NUMBER OF 3/4" DIA. SHEAR STUDS FOR COMPOSITE SLAB TO BEAM CONNECTION. SEE DECK SCHEDULE FOR LENGTH.
6. ALL STAIR FRAMING SHALL BE DESIGNED BY THE STAIR MANUFACTURER.
7. DENOTES FULLY RESTRAINED MOMENT CONNECTION. SEE 1/S512 FOR DETAILS.
8. SEE STRUCTURAL ELEVATIONS ON S200 FOR VERTICAL BRACING, GIRTS, HEADERS AND ADDITIONAL FRAMING INFORMATION.
9. PROVIDE (2) #3 BAR X 5'-0" AT REENTRANT SLAB CORNERS. SEE DETAIL 8/S510.
10. COORDINATE ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS.
11. SEE 2/S512 FOR MHE JUMPER BEAM DETAIL REQUIRED BELOW MHE POST LOADS ON MEZZ > 5 KIPS.

KEYPLAN



AECOM

PROJECT

HUMMINGBIRD

CENTRAL HUB GEN1.0 V1.1

2134 BLUE CREEK ROAD
HOGANSVILLE, GA 30230

CLIENT

SEEFRIED DEV. MANAGEMENT INC.
3333 RIVERWOOD PKWY, SUITE 200
ATLANTA, GA 30339

ARCHITECT

ARCHITECT OF RECORD
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

ENGINEERS/CONSULTANTS

STRUCTURAL
AECOM
277 Nationwide Blvd
Columbus, OH 43215
281.646.2400 tel
www.aecom.com

MEP
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

IT / SECURITY
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

FIRE PROTECTION / ALARM
AECOM
800 Gessner Rd
Houston, TX 77024
281.646.2400 tel
www.aecom.com

REGISTRATION

GEORGIA REGISTERED No. SE 001795 PROFESSIONAL ENGINEER ANDREW L. KNAPKE
3-07-25

03/07/2025

REV	DATE	ISSUED BY	ISSUED TO	DESCRIPTION
1	11/15/2024	AECOM	AHJ	ISSUE FOR BID & PERMIT
4	03/07/2025	AECOM	ATHENA	ADDENDUM #3

PROJECT NUMBER

60735057

SHEET TITLE

PARTIAL SPINE STRUCTURAL SECOND FLOOR FRAMING PLAN - AREA B1

SHEET NUMBER

S101.2B1

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

© 2024 AECOM Corporation

Autodesk Docs://BP-AMER (USA) 60735057 - ATS-GAZ5_Central Hub/60735057_ACM_R23_GAZ5_S.rvt

3/4/2025 3:40:08 PM

Printed on ___% Post-Consumer Recycled Content Paper